

Reference No: HDC(161)-CM/IU/2020/241
Addendum Date: 09th November 2020

ADDENDUM 1

Project Name: Development and Operation of Building for Clinics in Hulhumalé Lot 11628 (N3-25)

Proposal Reference Number: HDC(161)-CM/IU/2020/210

Announced Date: 24th October 2020

The following change(s) has been made to the RFP.

Section IV. Lessor's Requirements	Addition. Clause 5 - Quality Assurance Consultant Criteria (Refer to Next Page)
Section V. Contract Terms	Name Change. Section VI. Contract Terms
Section VI. Contract Terms Clause 18 – Duties and Obligation of Lessee	Addition. Clause 18.11 - The Lessee shall appoint locally registered Project Management (PM) consultant for the quality assurance of the building as per Section IV. Lessor's Requirements Clause 5 - Quality Assurance Consultant Criteria and be responsible to the Project Management Consultant.

Please include this addendum when submitting the proposal.






PLANNING & DEVELOPMENT DEPARTMENT

QUALITY ASSURANCE CONSULTANT CRITERIA



1.0 REQUIREMENTS OF THE CONSULTANT

Developer is required to hire a locally registered Project Management (PM) consultant for the quality assurance of the building. The PM consultant should be a 3rd party independent person or a firm that is locally registered under Ministry of National Planning, Housing & Infrastructure. This consultant should be unbiased in the works and while reporting to HDC. The consultant should be hired prior to the commencement of any site works. Once hired, the consultant should approve and submit a Construction Quality Management Plan (CQMP) from the Developer or Contractor before any physical works on site are carried. Duties and responsibilities of the consultant are as follows:

1.1 RESPONSIBILITIES

A. ASSURANCE OF CONSTRUCTION QUALITY

Necessary tests should be carried out on site and off site to ensure the quality of the final product. This includes, but not limited to compressive strength of concrete, tests done to ensure strength of steel, Slump test, Sieve Analysis and material specifications.

B. ASSURANCE OF FINISHING QUALITY

Consultant should ensure that the works are carried out according to the approved standards, methodologies, CQMP and drawings and if not mentioned as per the best practices followed. Consultant should also ensure that all works are carried out using approved materials which meets the standards as per the guidelines and the intended purpose for quality, safety and durability.

C. MATERIAL APPROVAL

All the materials used in the building structure, services and finishing shall be approved by the consultant. In approving the materials, the consultant shall ensure it meets the standards as per the guidelines and the intended purpose for quality, safety and durability. All the records of approved materials and its specifications should be kept and shared to HDC according to the reporting criteria.

D. APPROVE METHODOLOGIES

Prior to commencement of any construction works, Consultant should evaluate, suggest any improvements and approve method statements submitted by the developer. Consultant should ensure that the approved methodologies meet the intended purpose. All the methodology approvals should be kept on record and shared with HDC according to the reporting criteria.

E. ISSUING SITE INSTRUCTIONS

Issued site instructions should be recorded and submitted to HDC as per the reporting criteria.

F. APPROVE AS-BUILT DRAWINGS

The consultant should ensure the approved as-built drawings are accurate and meets onsite physical development.



2.2 REPORTING

All the following reports should be signed or stamped by the consultant. All the monthly reports should be submitted by the consultant before 10th of every month.

A. INITIAL REPORT

- i. Construction Quality Management Plan (CQMP)
- ii. Safety Plan
- iii. Work methodologies

B. MONTHLY REPORT

- i. Project Brief
- ii. Ongoing works and upcoming works for the next month
- iii. Overall construction progress showing the planned vs actual progress in the form of a Gantt chart
- iv. Accidents report
- v. Challenges faced during implementation
- vi. Test & Analysis reports
- vii. List of attended inspections and its reports
- viii. List of instructions given on site
- ix. Documentation of approved methodologies
- x. Documentation of approved materials

C. PROJECT COMPLETION REPORT

- i. Summary of Project
- ii. Challenges faced during the implementation
- iii. Maintenance requirements
- iv. Services systems manuals
- v. As-Built Drawings
- vi. Relevant authorities approvals such as MNDF, utilities and services and other relevant approvals.

